

BID TABULATION FOR:


HCMUD NO. 120 WATER PLANT NO. 1 REPAINTING
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 120
CITY OF HOUSTON E.T.J.
HARRIS COUNTY, TEXAS
JUNE 16, 2010
LJA ENGINEERING & SURVEYING, INC.
S. ROSS
JUNE 16, 2010
0451-1001 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL BID AMOUNT
1) M.K. PAINTING, INC.	\$56,400.00
2) W.W. PAYTON CORPORATION	\$68,000.00
3) UNIVERSAL COATING SPECIALISTS, LLC	\$102,800.00

CALENDAR DAYS - 60/80




I, David A. Rivera, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

HCMUD NO. 120 WATER PLANT NO. 1 REPAINTING
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 120
 CITY OF HOUSTON E.T.J.
 HARRIS COUNTY, TEXAS
 JUNE 16, 2010
 LJA ENGINEERING & SURVEYING, INC.
 S. ROSS
 JUNE 16, 2010
 0451-1001 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM DESCRIPTION	UNIT	QTY	1) M.K. PAINTING, INC.		2) W.W. PAYTON CORPORATION		3) UNIVERSAL COATING SPECIALISTS, LLC		
			UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	
BASE BID ITEMS									
1. FOR TWO (2) 20,000 GALLON HYDRO-PNEUMATIC TANK INTERIOR SURFACES, PROVIDE SSPC-SP5/NACE 1 WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH AN EPOXY COATING SYSTEM PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 8, COMPLETE IN PLACE	LS	1	\$21,000.00	\$21,000.00	\$22,000.00	\$22,000.00	\$31,400.00	\$31,400.00	
2. FOR TWO (2) 20,000 GALLON HYDRO-PNEUMATIC TANK EXTERIOR SURFACES, PROVIDE SSPC-SP10/NACE 2 NEAR WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH ZINC/EPOXY/URETHANE SYSTEM PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, COMPLETE IN PLACE	LS	1	\$21,000.00	\$21,000.00	\$15,000.00	\$15,000.00	\$35,800.00	\$35,800.00	
3. FOR ALL PLANT EXTERIOR PIPING, INCLUDING WELL HEADERS, PROVIDE SSPC-SP10/NACE NEAR-WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH ZINC/EPOXY/URETHANE SYSTEM PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, SURFACE PREPARATION AROUND PIPE VALVES OR JOINTS TO BE BY MECHANICAL, COMPLETE IN PLACE	LS	1	\$10,000.00	\$10,000.00	\$18,000.00	\$18,000.00	\$16,800.00	\$16,800.00	
4. COLLECTION AND DISPOSAL OF WASTE MATERIAL GENERATED BY THE COATING REMOVAL PROCESS, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$2,000.00	\$2,000.00	\$5,200.00	\$5,200.00	
5. FURNISH, OPERATE AND MAINTAIN DEHUMIDIFICATION SYSTEM DURING BLASTING, COATING AND CURING OF THE INTERIOR WET AREA, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$8,000.00	\$8,000.00	\$10,000.00	\$10,000.00	
SUBTOTAL BASE BID ITEMS				\$54,000.00		\$65,000.00		\$99,200.00	
MISCELLANEOUS ITEMS									
1. REPLACE HYDRO TANK ANCHOR BOLTS THAT HAVE COMPROMISED STRUCTURAL INTEGRITY (ONLY AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	10	\$50.00	\$500.00	\$75.00	\$750.00	\$100.00	\$1,000.00	
2. DISINFECTION OF HYDRO-PNEUMATIC TANKS, REQUIRED BACTERIOLOGICAL SAMPLING AND OBTAINING LABORATORY RESULTS, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$1,250.00	\$1,250.00	\$1,000.00	\$1,000.00	
3. REPAINT EXISTING METAL LOUVERS TO THE EXISTING CONTROL STRUCTURE, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$400.00	\$400.00	\$850.00	\$850.00	
4. WELDING AND/OR REPAIRS TO SIGHT GATE BOX ON HYDRO PNEUMATIC TANK (ONLY AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	6	\$150.00	\$900.00	\$100.00	\$600.00	\$125.00	\$750.00	
SUBTOTAL MISCELLANEOUS ITEMS				\$2,400.00		\$3,000.00		\$3,600.00	
BID SUMMARY									
SUBTOTAL BASE BID ITEMS				\$54,000.00		\$65,000.00		\$99,200.00	
SUBTOTAL MISCELLANEOUS ITEMS				\$2,400.00		\$3,000.00		\$3,600.00	
TOTAL AMOUNT BID				\$56,400.00		\$68,000.00		\$102,800.00	