


BID TABULATION FOR:

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
TO SERVE TELFAIR SECTIONS 25B AND 27B
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
NOVEMBER 2, 2011
LJA ENGINEERING, INC.
S. ROSS
NOVEMBER 2, 2011
0074-1009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL BID AMOUNT
1) JAHG, INC.	\$649,013.15
2) BAY UTILITIES, LLC	\$681,499.90
3) TRIPLE B SERVICES, L.L.P.	\$742,874.45
4) HURTADO CONSTRUCTION COMPANY	\$748,000.00
5) HARRIS CONSTRUCTION CO., LTD.	\$785,062.05

CALENDAR DAYS - 65/75



A handwritten signature in black ink, appearing to read "CJL", written over a horizontal line.

I, Christopher J. LeBlanc, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	1) JAHO, INC.		2) BAY UTILITIES, LLC		3) TRIPLE B SERVICES, L.L.P.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELFAR SECTION 27B WATER ITEMS									
1.	8" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	2,937	\$17.40	\$51,103.80	\$18.00	\$52,866.00	\$23.00	\$67,551.00
2.	6" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	50	\$29.85	\$1,492.50	\$12.00	\$600.00	\$16.00	\$800.00
3.	4" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	160	\$9.20	\$1,472.00	\$8.00	\$1,280.00	\$11.00	\$1,760.00
4.	FLUSHING VALVE UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE AND RESTRAINED JOINT FITTINGS, 6" VALVE & BOX, 6" LEAD AND FIRE HYDRANT, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	6	\$3,326.00	\$19,956.00	\$3,100.00	\$18,600.00	\$3,800.00	\$22,800.00
5.	CONNECT PROPOSED 8" WATER LINE TO EXISTING 8" WATER LINE, INCLUDING REMOVING EXISTING PLUG AND CLAMP AND VALVE AND ALL NECESSARY ADAPTERS AND CONNECTORS, COMPLETE IN PLACE	EA	2	\$270.00	\$540.00	\$250.00	\$500.00	\$330.00	\$660.00
6.	2" BLOW-OFF VALVE WITH BOX, COMPLETE IN PLACE	EA	1	\$594.00	\$594.00	\$680.00	\$680.00	\$460.00	\$460.00
7.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3,147	\$0.05	\$157.35	\$0.90	\$2,832.30	\$0.25	\$786.75
8.	FAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES TRENCH SAFETY, METER BOX, CURB STOP & ALL NECESSARY CONNECTORS & TAPS, COMPLETE IN PLACE	EA	26	\$810.00	\$21,060.00	\$660.00	\$17,160.00	\$715.00	\$18,590.00
9.	NEAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE, INCLUDES TRENCH SAFETY, METER BOX, CURB STOP AND ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	32	\$539.00	\$17,248.00	\$400.00	\$12,800.00	\$485.00	\$15,520.00
SUBTOTAL TELFAIR SECTION 27B WATER ITEMS					\$113,623.65		\$107,318.30		\$128,927.75
TELFAR SECTION 27B SANITARY SEWER ITEMS									
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 0' - 8' CUT, COMPLETE IN PLACE	LF	323	\$16.40	\$5,297.20	\$18.00	\$5,814.00	\$21.50	\$6,944.50
2.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 8' - 12' CUT, COMPLETE IN PLACE	LF	1,989	\$16.40	\$32,619.60	\$21.00	\$41,769.00	\$23.60	\$46,940.40
3.	PRECAST STANDARD SANITARY SEWER MANHOLE FOR 6" - 24" SANITARY SEWER PIPES, (8' DEPTH), COMPLETE IN PLACE	EA	17	\$1,603.00	\$27,251.00	\$1,900.00	\$32,300.00	\$2,240.00	\$38,080.00
4.	EXTRA DEPTH FOR SANITARY SEWER MANHOLE, (GREATER THAN 8' DEPTH), COMPLETE IN PLACE	VF	15	\$140.00	\$2,100.00	\$150.00	\$2,250.00	\$190.00	\$2,850.00
5.	SANITARY SEWER DROP, ALL DEPTHS AND SIZES, COMPLETE IN PLACE	EA	5	\$300.00	\$1,500.00	\$500.00	\$2,500.00	\$350.00	\$1,750.00
6.	"LONG SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, TRENCH SAFETY, CEMENT STABILIZED BACKFILL, RISER WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	19	\$1,322.00	\$25,118.00	\$1,100.00	\$20,900.00	\$1,950.00	\$37,050.00
7.	"SHORT SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, TRENCH SAFETY, ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	14	\$600.00	\$8,400.00	\$480.00	\$6,720.00	\$575.00	\$8,050.00
8.	STANDARD 6" SANITARY SEWER STACK, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$509.00	\$1,018.00	\$600.00	\$1,200.00	\$325.00	\$650.00
9.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2,312	\$0.05	\$115.60	\$0.90	\$2,080.80	\$0.25	\$578.00
10.	CONNECT PROPOSED 8" SANITARY SEWER TO EXISTING MANHOLE, INCLUDES CORING OF EXISTING MANHOLE & ADJUSTMENTS TO MATCH FINAL GRADE, COMPLETE IN PLACE	EA	2	\$1,458.00	\$2,916.00	\$930.00	\$1,860.00	\$700.00	\$1,400.00
11.	DEWATERING (0' - 16' DEPTH) FOR SANITARY SEWER CONSTRUCTION (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	2312	\$20.00	\$46,240.00	\$20.00	\$46,240.00	\$20.00	\$46,240.00
12.	ADDITIONAL COST FOR SANITARY SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	2,312	\$7.00	\$16,184.00	\$7.00	\$16,184.00	\$7.00	\$16,184.00
SUBTOTAL TELFAIR SECTION 27B SANITARY SEWER ITEMS					\$168,759.40		\$179,817.80		\$206,716.90

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) JAHO, INC.		2) BAY UTILITIES, LLC		3) TRIPLE B SERVICES, L.L.P.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELFAIR SECTION 27B DRAINAGE FACILITIES ITEMS									
1.	24" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	1,879	\$31.50	\$59,188.50	\$33.00	\$62,007.00	\$40.40	\$75,911.60
2.	30" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	525	\$39.85	\$20,921.25	\$42.00	\$22,050.00	\$50.80	\$26,670.00
3.	PRECAST OR CAST-IN-PLACE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	17	\$1,642.00	\$27,914.00	\$2,100.00	\$35,700.00	\$1,530.00	\$26,010.00
4.	STAGE I - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET, ("H-2"), ALL DEPTHS, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	16	\$594.00	\$9,504.00	\$750.00	\$12,000.00	\$860.00	\$13,760.00
5.	STAGE II - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET ("H-2"), COMPLETE IN PLACE	EA	16	\$648.00	\$10,368.00	\$1,100.00	\$17,600.00	\$900.00	\$14,400.00
6.	REMOVE EXISTING TYPE "E" INLET AND CONNECT EXISTING 30" R.C.P. TO PROPOSED 30" R.C.P. STORM SEWER, INCLUDES DISPOSAL OF ANY RESULTING MATERIAL OFFSITE AND DISPOSAL FEE, COMPLETE IN PLACE	LS	2	\$810.00	\$1,620.00	\$500.00	\$1,000.00	\$250.00	\$500.00
7.	UTILITY SPOILS, INCLUDES STRIPPING, STOCKPILING OF STRIPPINGS, HAULING EXCAVATED MATERIAL ON-SITE PER FILL PLAN TO 1/2 MILE, COMPACTION, AND REAPPLYING STRIPPINGS, COMPLETE IN PLACE	LS	1	\$10,368.00	\$10,368.00	\$4,400.00	\$4,400.00	\$600.00	\$600.00
8.	ADDITIONAL COST FOR STORM SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	2,404	\$7.00	\$16,828.00	\$7.00	\$16,828.00	\$7.00	\$16,828.00
9.	DEWATERING FOR STORM SEWER CONSTRUCTION (0'-16' DEPTH), (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	2,404	\$20.00	\$48,080.00	\$20.00	\$48,080.00	\$20.00	\$48,080.00
10.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2,404	\$0.05	\$120.20	\$0.90	\$2,163.60	\$0.25	\$601.00
11.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, COMPLETE IN PLACE	LS	1	\$567.00	\$567.00	\$1,000.00	\$1,000.00	\$300.00	\$300.00
SUBTOTAL TELFAIR SECTION 27B DRAINAGE FACILITIES ITEMS					\$205,478.95		\$222,828.60		\$223,660.60
TELFAIR SECTION 27B MISCELLANEOUS ITEMS									
1.	EXTRA CRUSHED LIMESTONE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00	\$15.00	\$1,500.00
2.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL DEPTHS, COMPLETE IN PLACE	CY	100	\$20.00	\$2,000.00	\$20.00	\$2,000.00	\$20.00	\$2,000.00
3.	ADDITIONAL RESTRAINED JOINT FITTINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
4.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE PLACED AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	5500	\$1.00	\$5,500.00	\$1.00	\$5,500.00	\$1.00	\$5,500.00
5.	CONSTRUCT AND MAINTAIN STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00
SUBTOTAL TELFAIR SECTION 27B MISCELLANEOUS ITEMS					\$11,500.00		\$11,500.00		\$11,500.00
TELFAIR SECTION 25B WATER ITEMS									
1.	8" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINTS FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	828	\$14.15	\$11,716.20	\$14.00	\$11,592.00	\$19.30	\$15,980.40
2.	FLUSHING VALVE UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE AND RESTRAINED JOINT FITTINGS, 6" VALVE & BOX, 6" LEAD AND FIRE HYDRANT, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	2	\$3,326.00	\$6,652.00	\$3,000.00	\$6,000.00	\$3,800.00	\$7,600.00
3.	CONNECT PROPOSED 8" WATER LINE TO EXISTING 8" WATER LINE, INCLUDING REMOVING EXISTING PLUG AND CLAMP AND VALVE, INCLUDES ALL NECESSARY ADAPTERS AND CONNECTORS, COMPLETE IN PLACE	EA	2	\$270.00	\$540.00	\$250.00	\$500.00	\$330.00	\$660.00
4.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	828	\$0.05	\$41.40	\$0.90	\$745.20	\$0.25	\$207.00
5.	FAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES TRENCH SAFETY, METER BOX, CURB STOP & ALL NECESSARY CONNECTORS & TAPS, COMPLETE IN PLACE	EA	9	\$811.00	\$7,299.00	\$600.00	\$5,400.00	\$725.00	\$6,525.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) JAHO, INC.		2) BAY UTILITIES, LLC		3) TRIPLE B SERVICES, L.L.P.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
6.	NEAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE, INCLUDES TRENCH SAFETY, METER BOX, CURB STOP AND ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	6	\$539.00	\$3,234.00	\$520.00	\$3,120.00	\$485.00	\$2,910.00
7.	ADJUST EXISTING GATE VALVE, COMPLETE IN PLACE	EA	1	\$162.00	\$162.00	\$110.00	\$110.00	\$100.00	\$100.00
SUBTOTAL TELFAIR SECTION 25B WATER ITEMS					\$29,644.60		\$27,467.20		\$33,982.40
TELFAIR SECTION 25B SANITARY SEWER ITEMS									
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 8' - 12' CUT, COMPLETE IN PLACE	LF	767	\$16.40	\$12,578.80	\$21.00	\$16,107.00	\$24.00	\$18,408.00
2.	PRECAST STANDARD SANITARY SEWER MANHOLE FOR 6" - 24" SANITARY SEWER PIPES, (8' DEPTH), COMPLETE IN PLACE	EA	5	\$1,604.00	\$8,020.00	\$1,900.00	\$9,500.00	\$2,235.00	\$11,175.00
3.	EXTRA DEPTH FOR SANITARY SEWER MANHOLE, (GREATER THAN 8' DEPTH), COMPLETE IN PLACE	VF	2	\$140.00	\$280.00	\$150.00	\$300.00	\$190.00	\$380.00
4.	"LONG SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, TRENCH SAFETY, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, CORING OF MANHOLE AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	3	\$1,291.00	\$3,873.00	\$1,200.00	\$3,600.00	\$1,660.00	\$4,980.00
5.	"SHORT SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, TRENCH SAFETY, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	4	\$565.00	\$2,260.00	\$500.00	\$2,000.00	\$550.00	\$2,200.00
6.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	767	\$0.05	\$38.35	\$0.90	\$690.30	\$0.25	\$191.75
7.	CONNECT PROPOSED 8" SANITARY SEWER TO EXISTING MANHOLE, INCLUDES CORING OF EXISTING MANHOLE, AND ADJUSTMENTS TO MATCH FINAL GRADE, COMPLETE IN PLACE	EA	1	\$1,458.00	\$1,458.00	\$930.00	\$930.00	\$700.00	\$700.00
8.	DEWATERING (0' - 16' DEPTH) FOR SANITARY SEWER CONSTRUCTION (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE E IN PLACE	LF	767	\$20.00	\$15,340.00	\$20.00	\$15,340.00	\$20.00	\$15,340.00
9.	ADDITIONAL COST FOR SANITARY SEWER BEDDING AND BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	767	\$7.00	\$5,369.00	\$7.00	\$5,369.00	\$7.00	\$5,369.00
SUBTOTAL TELFAIR SECTION 25B SANITARY SEWER ITEMS					\$49,217.15		\$53,836.30		\$58,743.75
TELFAIR SECTION 25B DRAINAGE FACILITIES ITEMS									
1.	24" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	693	\$31.75	\$22,002.75	\$33.00	\$22,869.00	\$45.60	\$31,600.80
2.	PRECAST OR CAST-IN-PLACE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	6	\$1,566.00	\$9,396.00	\$2,100.00	\$12,600.00	\$1,420.00	\$8,520.00
3.	STAGE I - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET, ("H-2"), ALL DEPTHS, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	6	\$594.00	\$3,564.00	\$750.00	\$4,500.00	\$860.00	\$5,160.00
4.	STAGE II - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET ("H-2"), COMPLETE IN PLACE	EA	6	\$648.00	\$3,888.00	\$1,100.00	\$6,600.00	\$900.00	\$5,400.00
5.	REMOVE EXISTING TYPE "E" INLET AND CONNECT PROP 24" R.C.P. TO EXIST. 24" R.C.P. STORM SEWER, INCLUDES DISPOSAL OF ANY RESULTING MATERIAL OFFSITE AND DISPOSAL FEE, COMPLETE IN PLACE	LS	1	\$810.00	\$810.00	\$500.00	\$500.00	\$250.00	\$250.00
6.	CONNECT PROP 24" R.C.P. TO EXIST. STORM SEWER MANHOLE, INCLUDES CORING OF MANHOLE, NON-SHRINK GROUT, COMPLETE IN PLACE	LS	1	\$1,080.00	\$1,080.00	\$1,200.00	\$1,200.00	\$700.00	\$700.00
7.	UTILITY SPOILS, INCLUDES STRIPPING, STOCKPILING OF STRIPPINGS, HAULING EXCAVATED MATERIAL ON-SITE PER FILL PLAN UP TO 1/2 MILE, COMPACTION, AND REAPPLYING STRIPPINGS, COMPLETE IN PLACE	LS	1	\$2,808.00	\$2,808.00	\$2,200.00	\$2,200.00	\$600.00	\$600.00
8.	ADDITIONAL COST FOR STORM SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	693	\$7.00	\$4,851.00	\$7.00	\$4,851.00	\$7.00	\$4,851.00
9.	DEWATERING FOR STORM SEWER CONSTRUCTION (0' - 16' DEPTH), (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	693	\$20.00	\$13,860.00	\$20.00	\$13,860.00	\$20.00	\$13,860.00
10.	TRENCH SAFETY SYSTEMS, ALL DEPTHS, COMPLETE IN PLACE	LF	693	\$0.05	\$34.65	\$0.90	\$623.70	\$0.25	\$173.25
11.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, COMPLETE IN PLACE	LS	1	\$567.00	\$567.00	\$1,000.00	\$1,000.00	\$300.00	\$300.00
SUBTOTAL TELFAIR SECTION 25B DRAINAGE FACILITIES ITEMS					\$62,861.40		\$70,803.70		\$71,415.05

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) JAHO, INC.		2) BAY UTILITIES, LLC		3) TRIPLE B SERVICES, L.L.P.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELFAR SECTION 25B MISCELLANEOUS ITEMS									
1.	EXTRA CRUSHED LIMESTONE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00	\$15.00	\$1,500.00
2.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL DEPTHS, COMPLETE IN PLACE	CY	100	\$20.00	\$2,000.00	\$20.00	\$2,000.00	\$20.00	\$2,000.00
3.	ADDITIONAL RESTRAINED JOINT FITTINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
4.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE PLACED AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	1,928	\$1.00	\$1,928.00	\$1.00	\$1,928.00	\$1.00	\$1,928.00
5.	CONSTRUCT AND MAINTAIN STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00
SUBTOTAL TELFAIR SECTION 25B MISCELLANEOUS ITEMS					\$7,928.00	\$7,928.00	\$7,928.00	\$7,928.00	\$7,928.00
BID SUMMARY									
SUBTOTAL TELFAIR SECTION 27B WATER ITEMS					\$113,623.65		\$107,318.30		\$128,927.75
SUBTOTAL TELFAIR SECTION 27B SANITARY SEWER ITEMS					\$168,759.40		\$179,817.80		\$206,716.90
SUBTOTAL TELFAIR SECTION 27B DRAINAGE FACILITIES ITEMS					\$205,478.95		\$222,828.60		\$223,660.60
SUBTOTAL TELFAIR SECTION 27B MISCELLANEOUS ITEMS					\$11,500.00		\$11,500.00		\$11,500.00
TELFAR SECTION 25B WATER ITEMS					\$29,644.60		\$27,467.20		\$33,982.40
SUBTOTAL TELFAIR SECTION 25B SANITARY SEWER ITEMS					\$49,217.15		\$53,836.30		\$58,743.75
SUBTOTAL TELFAIR SECTION 25B DRAINAGE FACILITIES ITEMS					\$62,861.40		\$70,803.70		\$71,415.05
SUBTOTAL TELFAIR SECTION 25B MISCELLANEOUS ITEMS					\$7,928.00		\$7,928.00		\$7,928.00
TOTAL AMOUNT BID					\$649,013.15		\$681,499.90		\$742,874.45

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)**

ITEM	DESCRIPTION	UNIT	QTY	4) HURTADO CONSTRUCTION COMPANY		5) HARRIS CONSTRUCTION CO., LTD.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELFAR SECTION 27B WATER ITEMS							
1.	8" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	2,937	\$21.70	\$63,732.90	\$19.00	\$55,803.00
2.	6" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	50	\$32.70	\$1,635.00	\$14.00	\$700.00
3.	4" PVC WATER PIPE, C-900, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINT FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	160	\$13.15	\$2,104.00	\$8.15	\$1,304.00
4.	FLUSHING VALVE UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE AND RESTRAINED JOINT FITTINGS, 6" VALVE & BOX, 6" LEAD AND FIRE HYDRANT, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	6	\$3,375.00	\$20,250.00	\$3,425.00	\$20,550.00
5.	CONNECT PROPOSED 8" WATER LINE TO EXISTING 8" WATER LINE, INCLUDING REMOVING EXISTING PLUG AND CLAMP AND VALVE AND ALL NECESSARY ADAPTERS AND CONNECTORS, COMPLETE IN PLACE	EA	2	\$300.00	\$600.00	\$150.00	\$300.00
6.	2" BLOW-OFF VALVE WITH BOX, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$450.00	\$450.00
7.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3,147	\$0.10	\$314.70	\$1.00	\$3,147.00
8.	FAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES TRENCH SAFETY, METER BOX, CURB STOP & ALL NECESSARY CONNECTORS & TAPS, COMPLETE IN PLACE	EA	26	\$1,100.00	\$28,600.00	\$965.00	\$25,090.00
9.	NEAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE, INCLUDES TRENCH SAFETY, METER BOX, CURB STOP AND ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	32	\$462.00	\$14,784.00	\$485.00	\$15,520.00
SUBTOTAL TELFAIR SECTION 27B WATER ITEMS					\$133,020.60		\$122,864.00
TELFAR SECTION 27B SANITARY SEWER ITEMS							
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 0' - 8' CUT, COMPLETE IN PLACE	LF	323	\$20.50	\$6,621.50	\$19.05	\$6,153.15
2.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 8' - 12' CUT, COMPLETE IN PLACE	LF	1,989	\$21.50	\$42,763.50	\$20.75	\$41,271.75
3.	PRECAST STANDARD SANITARY SEWER MANHOLE FOR 6" - 24" SANITARY SEWER PIPES, (8' DEPTH), COMPLETE IN PLACE	EA	17	\$2,500.00	\$42,500.00	\$2,930.00	\$49,810.00
4.	EXTRA DEPTH FOR SANITARY SEWER MANHOLE, (GREATER THAN 8' DEPTH), COMPLETE IN PLACE	VF	15	\$110.00	\$1,650.00	\$240.00	\$3,600.00
5.	SANITARY SEWER DROP, ALL DEPTHS AND SIZES, COMPLETE IN PLACE	EA	5	\$350.00	\$1,750.00	\$375.00	\$1,875.00
6.	"LONG SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, TRENCH SAFETY, CEMENT STABILIZED BACKFILL, RISER WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	19	\$1,550.00	\$29,450.00	\$1,685.00	\$32,015.00
7.	"SHORT SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, TRENCH SAFETY, ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	14	\$535.00	\$7,490.00	\$525.00	\$7,350.00
8.	STANDARD 6" SANITARY SEWER STACK, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$555.00	\$1,110.00	\$395.00	\$790.00
9.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2,312	\$0.10	\$231.20	\$1.00	\$2,312.00
10.	CONNECT PROPOSED 8" SANITARY SEWER TO EXISTING MANHOLE, INCLUDES CORING OF EXISTING MANHOLE & ADJUSTMENTS TO MATCH FINAL GRADE, COMPLETE IN PLACE	EA	2	\$800.00	\$1,600.00	\$725.00	\$1,450.00
11.	DEWATERING (0' - 16' DEPTH) FOR SANITARY SEWER CONSTRUCTION (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	2312	\$20.00	\$46,240.00	\$20.00	\$46,240.00
12.	ADDITIONAL COST FOR SANITARY SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	2,312	\$7.00	\$16,184.00	\$7.00	\$16,184.00
SUBTOTAL TELFAIR SECTION 27B SANITARY SEWER ITEMS					\$197,590.20		\$209,050.90

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	4) HURTADO CONSTRUCTION COMPANY		5) HARRIS CONSTRUCTION CO., LTD.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELF AIR SECTION 27B DRAINAGE FACILITIES ITEMS							
1.	24" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	1,879	\$38.20	\$71,777.80	\$45.00	\$84,555.00
2.	30" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	525	\$47.20	\$24,780.00	\$63.00	\$33,075.00
3.	PRECAST OR CAST-IN-PLACE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	17	\$2,000.00	\$34,000.00	\$2,325.00	\$39,525.00
4.	STAGE I - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET, ("H-2"), ALL DEPTHS, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	16	\$690.00	\$11,040.00	\$525.00	\$8,400.00
5.	STAGE II - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET ("H-2"), COMPLETE IN PLACE	EA	16	\$1,100.00	\$17,600.00	\$1,075.00	\$17,200.00
6.	REMOVE EXISTING TYPE "E" INLET AND CONNECT EXISTING 30" R.C.P. TO PROPOSED 30" R.C.P. STORM SEWER, INCLUDES DISPOSAL OF ANY RESULTING MATERIAL OFFSITE AND DISPOSAL FEE, COMPLETE IN PLACE	LS	2	\$500.00	\$1,000.00	\$850.00	\$1,700.00
7.	UTILITY SPOILS, INCLUDES STRIPPING, STOCKPILING OF STRIPPINGS, HAULING EXCAVATED MATERIAL ON-SITE PER FILL PLAN TO 1/2 MILE, COMPACTION, AND REAPPLYING STRIPPINGS, COMPLETE IN PLACE	LS	1	\$5,511.20	\$5,511.20	\$12,285.00	\$12,285.00
8.	ADDITIONAL COST FOR STORM SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	2,404	\$7.00	\$16,828.00	\$7.00	\$16,828.00
9.	DEWATERING FOR STORM SEWER CONSTRUCTION (0'-16' DEPTH), (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	2,404	\$20.00	\$48,080.00	\$20.00	\$48,080.00
10.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2,404	\$0.10	\$240.40	\$1.00	\$2,404.00
11.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, COMPLETE IN PLACE	LS	1	\$600.00	\$600.00	\$850.00	\$850.00
SUBTOTAL TELFAIR SECTION 27B DRAINAGE FACILITIES ITEMS					\$231,457.40		\$264,902.00
TELF AIR SECTION 27B MISCELLANEOUS ITEMS							
1.	EXTRA CRUSHED LIMESTONE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00
2.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL DEPTHS, COMPLETE IN PLACE	CY	100	\$20.00	\$2,000.00	\$20.00	\$2,000.00
3.	ADDITIONAL RESTRAINED JOINT FITTINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
4.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE PLACED AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	5500	\$1.00	\$5,500.00	\$1.00	\$5,500.00
5.	CONSTRUCT AND MAINTAIN STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00
SUBTOTAL TELFAIR SECTION 27B MISCELLANEOUS ITEMS					\$11,500.00		\$11,500.00
TELF AIR SECTION 25B WATER ITEMS							
1.	8" PVC WATER PIPE, C-800, DR 18, CLASS 150, ALL DEPTHS, INCLUDES RESTRAINED JOINTS FITTINGS (VALVES, TEES, BENDS, PLUGS, ETC.), REDUCERS, CONCRETE PADS, AND CONNECTORS, COMPLETE IN PLACE	LF	828	\$18.65	\$15,442.20	\$15.00	\$12,420.00
2.	FLUSHING VALVE UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE AND RESTRAINED JOINT FITTINGS, 6" VALVE & BOX, 6" LEAD AND FIRE HYDRANT, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	2	\$3,355.00	\$6,710.00	\$3,425.00	\$6,850.00
3.	CONNECT PROPOSED 8" WATER LINE TO EXISTING 8" WATER LINE, INCLUDING REMOVING EXISTING PLUG AND CLAMP AND VALVE, INCLUDES ALL NECESSARY ADAPTERS AND CONNECTORS, COMPLETE IN PLACE	EA	2	\$300.00	\$600.00	\$150.00	\$300.00
4.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	828	\$0.10	\$82.80	\$1.00	\$828.00
5.	FAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES TRENCH SAFETY, METER BOX, CURB STOP & ALL NECESSARY CONNECTORS & TAPS, COMPLETE IN PLACE	EA	9	\$1,150.00	\$10,350.00	\$965.00	\$8,685.00

BID TABULATION FOR:

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	4) HURTADO CONSTRUCTION COMPANY		5) HARRIS CONSTRUCTION CO., LTD.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
6.	NEAR SIDE, SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE, INCLUDES TRENCH SAFETY, METER BOX, CURB STOP AND ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	6	\$503.00	\$3,018.00	\$485.00	\$2,910.00
7.	ADJUST EXISTING GATE VALVE, COMPLETE IN PLACE	EA	1	\$400.00	\$400.00	\$150.00	\$150.00
SUBTOTAL TELFAIR SECTION 25B WATER ITEMS					\$36,603.00		\$32,143.00
TELF AIR SECTION 25B SANITARY SEWER ITEMS							
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 8' - 12' CUT, COMPLETE IN PLACE	LF	767	\$23.50	\$18,024.50	\$22.45	\$17,219.15
2.	PRECAST STANDARD SANITARY SEWER MANHOLE FOR 6" - 24" SANITARY SEWER PIPES, (8' DEPTH), COMPLETE IN PLACE	EA	5	\$2,500.00	\$12,500.00	\$2,925.00	\$14,625.00
3.	EXTRA DEPTH FOR SANITARY SEWER MANHOLE, (GREATER THAN 8' DEPTH), COMPLETE IN PLACE	VF	2	\$110.00	\$220.00	\$240.00	\$480.00
4.	"LONG SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, TRENCH SAFETY, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, CORING OF MANHOLE AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	3	\$1,640.00	\$4,920.00	\$1,685.00	\$5,055.00
5.	"SHORT SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM 2241, SDR 26, ALL DEPTHS, INCLUDING PIPE, CEMENT STABILIZED BACKFILL, RISER, WYE, PLUG, MARKER, TRENCH SAFETY, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	4	\$480.00	\$1,920.00	\$525.00	\$2,100.00
6.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	767	\$0.10	\$76.70	\$1.00	\$767.00
7.	CONNECT PROPOSED 8" SANITARY SEWER TO EXISTING MANHOLE, INCLUDES CORING OF EXISTING MANHOLE, AND ADJUSTMENTS TO MATCH FINAL GRADE, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00	\$725.00	\$725.00
8.	DEWATERING (0' - 16' DEPTH) FOR SANITARY SEWER CONSTRUCTION (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE E IN PLACE	LF	767	\$20.00	\$15,340.00	\$20.00	\$15,340.00
9.	ADDITIONAL COST FOR SANITARY SEWER BEDDING AND BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	767	\$7.00	\$5,369.00	\$7.00	\$5,369.00
SUBTOTAL TELFAIR SECTION 25B SANITARY SEWER ITEMS					\$59,170.20		\$61,680.15
TELF AIR SECTION 25B DRAINAGE FACILITIES ITEMS							
1.	24" RCP, STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, COMPLETE IN PLACE	LF	693	\$37.10	\$25,710.30	\$40.00	\$27,720.00
2.	PRECAST OR CAST-IN-PLACE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	6	\$2,000.00	\$12,000.00	\$2,095.00	\$12,570.00
3.	STAGE I - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET, ("H-2"), ALL DEPTHS, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	6	\$690.00	\$4,140.00	\$525.00	\$3,150.00
4.	STAGE II - STANDARD 5' REINFORCED CONCRETE PRECAST OR CAST-IN-PLACE INLET ("H-2"), COMPLETE IN PLACE	EA	6	\$1,100.00	\$6,600.00	\$1,075.00	\$6,450.00
5.	REMOVE EXISTING TYPE "E" INLET AND CONNECT PROP 24" R.C.P. TO EXIST. 24" R.C.P. STORM SEWER, INCLUDES DISPOSAL OF ANY RESULTING MATERIAL OFFSITE AND DISPOSAL FEE, COMPLETE IN PLACE	LS	1	\$600.00	\$600.00	\$850.00	\$850.00
6.	CONNECT PROP 24" R.C.P. TO EXIST. STORM SEWER MANHOLE, INCLUDES CORING OF MANHOLE, NON-SHRINK GROUT, COMPLETE IN PLACE	LS	1	\$800.00	\$800.00	\$1,000.00	\$1,000.00
7.	UTILITY SPOILS, INCLUDES STRIPPING, STOCKPILING OF STRIPPINGS, HAULING EXCAVATED MATERIAL ON-SITE PER FILL PLAN UP TO 1/2 MILE, COMPACTION, AND REAPPLYING STRIPPINGS, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$3,350.00	\$3,350.00
8.	ADDITIONAL COST FOR STORM SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, (TO BE USED ONLY AT WRITTEN DIRECTION OF ENGINEER), COMPLETE IN PLACE	LF	693	\$7.00	\$4,851.00	\$7.00	\$4,851.00
9.	DEWATERING FOR STORM SEWER CONSTRUCTION (0' - 16' DEPTH), (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	693	\$20.00	\$13,860.00	\$20.00	\$13,860.00
10.	TRENCH SAFETY SYSTEMS, ALL DEPTHS, COMPLETE IN PLACE	LF	693	\$0.10	\$69.30	\$1.00	\$693.00
11.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, COMPLETE IN PLACE	LS	1	\$600.00	\$600.00	\$500.00	\$500.00
SUBTOTAL TELFAIR SECTION 25B DRAINAGE FACILITIES ITEMS					\$70,730.60		\$74,994.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE TELFAIR SECTIONS 25B AND 27B
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 139
 CITY OF SUGAR LAND, FORT BEND COUNTY, TEXAS
 NOVEMBER 2, 2011
 LJA ENGINEERING, INC.
 S. ROSS
 NOVEMBER 2, 2011
 0074-1009 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	4) HURTADO CONSTRUCTION COMPANY		5) HARRIS CONSTRUCTION CO., LTD.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
TELFAIR SECTION 25B MISCELLANEOUS ITEMS							
1.	EXTRA CRUSHED LIMESTONE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00
2.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL DEPTHS, COMPLETE IN PLACE	CY	100	\$20.00	\$2,000.00	\$20.00	\$2,000.00
3.	ADDITIONAL RESTRAINED JOINT FITTINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
4.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE PLACED AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	1,928	\$1.00	\$1,928.00	\$1.00	\$1,928.00
5.	CONSTRUCT AND MAINTAIN STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00
SUBTOTAL TELFAIR SECTION 25B MISCELLANEOUS ITEMS					\$7,928.00	\$7,928.00	
BID SUMMARY							
SUBTOTAL TELFAIR SECTION 27B WATER ITEMS					\$133,020.60		\$122,864.00
SUBTOTAL TELFAIR SECTION 27B SANITARY SEWER ITEMS					\$197,590.20		\$209,050.90
SUBTOTAL TELFAIR SECTION 27B DRAINAGE FACILITIES ITEMS					\$231,457.40		\$264,902.00
SUBTOTAL TELFAIR SECTION 27B MISCELLANEOUS ITEMS					\$11,500.00		\$11,500.00
TELFAIR SECTION 25B WATER ITEMS					\$36,803.00		\$32,143.00
SUBTOTAL TELFAIR SECTION 25B SANITARY SEWER ITEMS					\$59,170.20		\$61,680.15
SUBTOTAL TELFAIR SECTION 25B DRAINAGE FACILITIES ITEMS					\$70,730.60		\$74,994.00
SUBTOTAL TELFAIR SECTION 25B MISCELLANEOUS ITEMS					\$7,928.00		\$7,928.00
TOTAL AMOUNT BID					\$748,000.00		\$785,062.05

