

ADDENDUM NO. 1


**CONSTRUCTION OF
SANITARY FORCE MAIN
TO SERVE
THE WOODLANDS 400 ACRE TRACT
HARRIS - MONTGOMERY COUNTIES MUNICIPAL UTILITY DISTRICT NO. 386
THE WOODLANDS
MONTGOMERY COUNTY, TEXAS**

May 6, 2010

Job No. 0472-7003A-401C

The following changes will be considered part of the Plans, Construction and Bid Documents:

1. Reference: Bid Proposal
 - Replace Pages PB-3 and PB-4 with revised Pages PB-3 and PB-4 (Attached).
2. Clarification:
 - Contractor should bid from the plans signed and dated by the engineer on June 10, 2009.
3. Clarification:
 - All utility spoils to be hauled and disposed off site.



Don Allen Reed II
5/7/10

ADDENDUM NO. 1
FRN F-1386
LJA Engineering & Surveying, Inc.

**BID SCHEDULE
FOR CONSTRUCTION OF
SANITARY FORCE MAIN
TO SERVE
THE WOODLANDS 400 ACRE TRACT
HARRIS - MONTGOMERY COUNTIES MUNICIPAL UTILITY DISTRICT NO. 386**

DIVISION I - SANITARY SEWER COLLECTION SYSTEM

The Contractor is to fully understand that the Unit Price shall include a sufficient allowance for the completion of all work bid upon, including all labor, materials, excavation, incidentals, pipe bedding, special backfill, clean up, disposal of excess excavated material, and all clearing and grubbing, if any.

Item	Quantity	Unit	Description	Unit Price	Material Cost	Labor & Equip. Cost	Total Cost
1.	5,895	LF	12" Force Main, PVC C900 DR18, Including Excavation, Bedding, Backfill (Acceptable bank sand will be allowed for alternative bedding material as directed by the Engineer) and Fittings @ _____dollars _____cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
2.	737	LF	20" Steel Casing for 12" @ Force Main _____dollars _____cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
3.	4	EA	Air Release Valve for 12" Force Main @ _____dollars _____cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
4.	1,285	LF	Auger for 12" Force Main, "Does Not Include" 12" Forcemain, PVC C-900 DR18 @ _____dollars _____cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
5.	132	LF	Auger for 20" Steel Casing, "Does Not Include" Including 12" Forcemain, PVC C-900 DR18 @ _____dollars _____cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
6.	2	EA	Remove and Dispose of Existing Sanitary Sewer Plug and Connect Proposed 12" Force Main @ _____dollars _____cents per unit.	\$ _____	\$ _____	\$ _____	\$ _____

Addendum No. 1

BID SCHEDULE - CONTINUED
SANITARY FORCE MAIN
JOB NO. 0472-7003A-401C
DIVISION I – SANITARY SEWER COLLECTION SYSTEM

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Description</u>	<u>Unit Price</u>	<u>Material Cost</u>	<u>Labor & Equip. Cost</u>	<u>Total Cost</u>
7.	238	LF	12" PVC Force Main Assembly with Restrained Joints (AWWA C-900 DR 14), Class 200, Includes All Bends and Adapters @ _____ dollars _____ cents per unit.	\$ _____	\$ _____	\$ _____	\$ _____
8.	3,975	LF	Regrade and Seed Existing Roadside Ditch @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
9.	1,290	LF	Regrade and Seed Existing Collector Swale @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
10.	700	LF	Regrade and Seed Existing Sanitary Sewer Easement @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
11.	5,895	LF	Trench Safety System (All Depths) @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
12.	9	EA	Remove and Dispose of Existing Roadside Ditch Drop Structure and Construct Proposed Channel Lock Drop Structure @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____
13.	1	LS	Storm Water Pollution Prevention Plan, Includes Filter Fabric Fencing, Inlet Protection and Construction Entrances (All Sizes) @ _____ dollars _____ cents per unit	\$ _____	\$ _____	\$ _____	\$ _____

Addendum No. 1