

**ADDENDUM NO. 1
CONSTRUCTION OF THE
WATER, SANITARY SEWER AND DRAINAGE FACILITIES
TO SERVE
MAGNOLIA CREEK SECTION ELEVEN PHASE ONE
MHWS DEVELOPMENT, LLC ON BEHALF OF
GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 6
CITY OF LEAGUE CITY
GALVESTON COUNTY, TEXAS**

AUGUST 17, 2010

LJA JOB NO. 1742-611AD (9.4)

The following changes will be considered part of the Construction Plans, Bid Proposal and Contract Documents:

1.) Reference: **Contract Documents – Bid Proposal**

Replace: Page 9 of 23 with revised Page 9 of 23 (attached).

There are no other changes or revisions to the Construction Plans, Bid Proposal and Contract Documents at this time.



**PROPOSAL BIDDING SHEET – CONTINUED
 CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 TO SERVE MAGNOLIA CREEK SECTION ELEVEN PHASE ONE
 MHWS DEVELOPMENT, LLC ON BEHALF OF G.C.M.U.D. NO. 6
 CITY OF LEAGUE CITY, GALVESTON COUNTY, TEXAS
 LJA JOB NO. 1742-611AD**

STORM SEWER ITEMS

ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION AND TOTAL WRITTEN UNIT PRICE	UNIT PRICE	AMOUNT
17.	2,085	LF	Trench Safety, (All Depths), Complete in place	\$ _____	\$ _____
18.	2	EA	Cast In Place Type "H-2" Inlet, See Details on Plans, All Depths, Complete in place	\$ _____	\$ _____
19.	5,600	CY	Utility Spoils to be Utilized as Fill on Site, Includes Compaction to 95% Standard Proctor Density in Maximum 8" Lifts as per Grading Plan Sheet (7 of 33), Complete in place	\$ _____	\$ _____
20.	2,865	CY	Utility Spoils to be Hauled Using Off-Road Trucks to Adjacent Future Magnolia Creek Section 11 Phase II, Placed and Compacted to 95% Standard Proctor Density, Complete in place	\$ _____	\$ _____
21.	31	EA	Stage II – Inlet Protection Barriers, (Includes Burlap Bags for Erosion and Sediment Control), Complete in place	\$ _____	\$ _____
22.	36	SY	Remove and Relocate Existing Rip Rap to Location within Magnolia Creek Development, Complete in place	\$ _____	\$ _____
SUBTOTAL STORM SEWER ITEMS				\$ _____	