

**ADDENDUM NO. 1
CONSTRUCTION OF THE
WATER PLANT CHLORAMINE
DISINFECTION SYSTEM CONVERSION
TO SERVE FORT BEND COUNTY M.U.D. NO. 122
CITY OF HOUSTON E.T.J.
FORT BEND COUNTY, TEXAS**

August 16, 2010

LJA JOB NO. 1786-0901 (9.4)

The following changes will be considered part of the Construction Plans, Bid Proposal and Contract Documents:

1.) Reference: **Contract Documents – Bid Proposal**

Replace: Pages 2, 3, and 4 of 7 with revised Pages 2, 3, and 4 of 7 (attached).

There are no other changes or revisions to the Construction Plans, Bid Proposal and Contract Documents at this time.



Vinoth Manoharan
08/17/10

PROPOSAL BIDDING SHEET

**CONSTRUCTION OF THE
WATER PLANT CHLORAMINE
DISINFECTION SYSTEM CONVERSION
TO SERVE FORT BEND COUNTY M.U.D. NO. 122
CITY OF HOUSTON E.T.J.
FORT BEND COUNTY, TEXAS
LJA JOB NO. 1786-0901**

Gentlemen:

Pursuant to the foregoing Invitation and Instructions to Bidders, the undersigned bidder hereby proposes to do all the work for the unit prices bid to furnish all necessary superintendence, labor, machine, equipment, tools, materials, insurance and miscellaneous items, to complete all work according to the bids, as provided in the construction plan and contract documents for the construction of the Water Plant Chloramine Disinfection System Conversion to Serve Fort Bend County M.U.D. No. 122, and clean up the site to the satisfaction of the Owner/Engineer, and bind himself on acceptance of this proposal to execute a contract and bonds for completing said project within the time stated for the following prices, to wit:

BASE BID ITEMS

ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT
1.	1	LS	Site Work, Including Re-Seeding and Re-Grading Disturbed Areas, Complete in place	\$ _____	\$ _____
2.	1	LS	Fiberglass Building and Emergency Shower/Eyewash Station, Including Concrete Slab, 2-Inch Water Line, Sidewalk , and All Appurtenances, Complete in place	\$ _____	\$ _____
3.	1	LS	Chlorination System, Including Two Automatic Chlorinator Assemblies, 1-Inch Sch. 80 PVC Pipe Cl ₂ Feed Line, Chemical Injection Assembly, Connection to Existing Chlorination System, and All Appurtenances, Complete in place	\$ _____	\$ _____
4.	1	LS	LAS Feed System, Including Four (4) Automatic Vacuum Liquid Dosers, 1-Inch Sch. 80 PVC Pipe LAS Feed Lines, Two Chemical Injection Assemblies, 540 Gallon Double Walled UV Resistant Tank, Ultrasonic Level Detection System, Leak Detection System, and All Appurtenances, Complete in place	\$ _____	\$ _____

PROPOSAL BIDDING SHEET - CONTINUED
 WATER PLANT CHLORAMINE DISINFECTION SYSTEM
 CONVERSION TO SERVE FORT BEND COUNTY M.U.D. NO. 122
 CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS
 LJA JOB NO. 1786-0901

BASE BID ITEMS

ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT
5.	1	LS	Chloramine Analyzer System, Including Two Analyzers, 1-Inch Sch. 80 PVC Pipe Sample/Return/Waste Lines, Four Sample Water Suction/Return Assemblies, Booster Pump, Two (2) 25-Gallon Containers with Lid for Waste Collection, Concrete Slab, and All Appurtenances, Complete in place	\$ _____	\$ _____
6.	388	LF	12-Inch Ductile Iron Surface Water Line, Including Valves, Fittings, Pipe Supports, Thrust Blocks, Sample Cocks, Pipe Clamps, Connection to Surface Water Line, and All Appurtenances, Complete in place	\$ _____	\$ _____
7.	352	LF	Trench Safety System, Complete in place	\$ _____	\$ _____
8.	1	EA	Modifications to Existing Ground Storage Tanks Including Connections of 12" Surface Water Lines, Installation of 20" Double Gooseneck Roof Vent with 16 Mesh Stainless Steel Screen, Complete in place	\$ _____	\$ _____
9.	1	LS	Storm Water Pollution Prevention Items, Complete in place	\$ _____	\$ _____

PROPOSAL BIDDING SHEET - CONTINUED
WATER PLANT CHLORAMINE DISINFECTION SYSTEM
CONVERSION TO SERVE FORT BEND COUNTY M.U.D. NO. 122
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS
LJA JOB NO. 1786-0901

BASE BID ITEMS

ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT
10.	1	LS	Electrical Control Panel, Receptacles, Instruments, Autosensory Controls, Telephone Autodialer, Conduit, and Furnish All Appurtenances for a Complete Operating System, Complete in place	\$ _____	\$ _____
11.	95	LF	12-Inch Steel Pipe Water Line, Including Valves, Fittings, Pipe Supports, Pipe Clamps, and All Appurtenances, Complete in place	\$ _____	\$ _____
SUBTOTAL BASE BID ITEMS				\$ _____	