

**ADDENDUM NO. 1**  
**FOR**  
**GALVESTON COUNTY WATER CONTROL**  
**AND**  
**IMPROVEMENT DISTRICT NO. 12**  
**GENERATOR ACQUISITION**  
**LJA Project No. E125-0020-905**

**March 10, 2010**

**CONTRACT DOCUMENTS:**

1. **Bid Item No. 1, Mobile Generator** – The 150 kw Generator (Diesel) will have a voltage selector switch mounted on the unit capable of pre-setting electrical loads to 480v, 3 phase. Generator will have 2 locations for 110v – 120v electrical receptacles.
  
2. **Bid Item No. 2, Lump Sum Appurtenances:**  

Clarification – Transfer switch (manual) will not be mounted on Mobile Trailer Package.

Clarification – Lights will be mounted on the Mobile Trailer per State of Texas requirements only.

Clarification - Pigtail Couplings; one will be mounted on the Mobile Trailer compatible to a connecting pigtail coupling installed by the Contractor at each of the 3 locations listed.

All appurtenances required to complete Mobile Generator connections to the 3 locations will be provided by the Contractor.
  
3. **Bid Item No. 3, Tandem Axle Trailer** – Contractor will provide electrical wiring (40 L.F.) with correct pigtails to each of the 3 locations.  

Contractor will have water-proof metal box installed on mobile generator tandem axle trailer to store the electrical cables.

**SPECIFICATIONS:**

Item No. 16045 – Manual Transfer Switch, **DELETE** second paragraph under GENERAL and **INSERT** the following:

A manual transfer switch will be installed by the Contractor at each of the following locations (3 each):

- (1) Water Well – 905 Vivan Street, 60 HP and electrical is 440v, 3 Phase.
- (2) Water Well – 901 SH 146, 50 HP and electrical is 280/460v, 3 Phase.
- (3) Lift Station – 201 FM 2094, 2 Each 60 HP Pumps – 480v, 3 Phase.
- (4) Amperage – 40 to 1000 Amps (Standard Transition).

END OF ADDENDUM NO. 1