

Bid Tabulation - Bid Opening, Thursday, March 4, 2010 at 2:00 P.M.
 City of La Porte
 South Broadway Waterline Replacement
 La Porte Bid No. 10021
 LJA Project No. E170-0070

D. L. Elliott Enterprises, Inc.
 13405 S.W. Freeway, Ste 210
 Sugar Land, TX 77478
 PH: 281-277-4414
 FAX: 281-277-3698
 Darryl Elliott, President

Metro City Construction, L.P.
 5715 Luce Street
 Houston, TX 77087
 PH: 713-943-0090
 FAX: 713-943-0092
 Robert N. Smither, Chief Estim.

Mar-Con Services, LLC
 1410 Preston Avenue, Bldg. H
 Pasadena, TX 77503
 PH: 713-473-1800
 FAX: 713-473-1811
 Mario Ramos, Owner

Kingsley Constructors, Inc.
 1544 Sawdust Rd., Suite 200
 Houston, TX 77380
 PH: 281-363-1979
 FAX: 281-363-1993
 Brad C. Kingsley, VP

Pro Line Service
 P.O. Box 6853
 Kingwood, TX 77325
 PH: 832-473-2905
 FAX: 281-312-1346
 Courtland Peacock, President

ITEM NO.	DESCRIPTION	EST. QTY.	UNITS	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM
1	8-Inch Waterline (PVC, AWWA C-900, DR-18) with Ductile Iron Fittings, Open Cut, Joint Restraints (as necessary), All Depths, Complete in Place.	300	L.F.	\$33.00	\$9,900.00	\$51.00	\$15,300.00	\$47.10	\$14,130.00	\$23.00	\$6,900.00	\$49.00	\$14,700.00
2	6-Inch Waterline (PVC, AWWA C-900, DR-18) with Ductile Iron Fittings, Open Cut, Joint Restraints (as necessary), all Depths, Complete in Place.	16	L.F.	\$80.00	\$1,280.00	\$63.40	\$1,014.40	54.00	\$864.00	100.00	\$1,600.00	58.00	\$928.00
3	2-Inch Waterline (PVC, Sch. 40 with Sch. 40 Fittings), Open Cut, Joint Restraints (as necessary), All Depths, Complete in Place.	18	L.F.	\$28.00	\$504.00	\$12.20	\$219.60	\$20.00	\$360.00	\$20.00	\$360.00	\$29.00	\$522.00
4	8-Inch Waterline, Augered Construction (PVC, AWWA C-900, DR-18) All Depths, Complete in Place.	2,388	L.F.	\$36.00	\$85,968.00	\$35.10	\$83,818.80	\$38.50	\$91,938.00	\$43.00	\$102,684.00	\$54.00	\$128,952.00
5	8" Gate Valve (AWWA) with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	7	EA.	\$1,050.00	\$7,350.00	\$1,518.00	\$10,626.00	\$1,356.00	\$9,492.00	\$1,500.00	\$10,500.00	\$900.00	\$6,300.00
6	2" Gate Valve (AWWA) with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	1	EA.	\$350.00	\$350.00	\$496.00	\$496.00	\$600.00	\$600.00	\$450.00	\$450.00	\$300.00	\$300.00
7	8" Tapping sleeve and Valve (AWWA) Full body with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	1	EA.	\$4,000.00	\$4,000.00	\$5,364.00	\$5,364.00	\$4,000.00	\$4,000.00	\$4,000.00	\$4,000.00	\$2,800.00	\$2,800.00
8	Fire Hydrant Assembly, With Restrained Joints, 4-Foot Bury, Concrete Collar, Complete in Place.	5	EA.	\$2,700.00	\$13,500.00	\$3,307.00	\$16,535.00	\$3,200.00	\$16,000.00	\$4,000.00	\$20,000.00	\$2,800.00	\$14,000.00
9	Extra Depth Bury for Fire Hydrant, Complete in Place.	10	V.F.	\$60.00	\$600.00	\$69.50	\$695.00	\$85.00	\$850.00	\$100.00	\$1,000.00	\$60.00	\$600.00
10	Wet connections (8-Inch), Includes Cut and Plug of Existing Pipes (All Sizes), With Backfill, Complete in Place.	3	EA.	\$900.00	\$2,700.00	\$1,035.00	\$3,105.00	\$660.00	\$1,980.00	\$1,200.00	\$3,600.00	\$800.00	\$2,400.00
11	Wet Connections (6-Inch), Includes Cut and Plug of Existing Pipes (all Sizes), with Backfill, Complete in Place.	2	EA.	\$800.00	\$1,600.00	\$838.00	\$1,676.00	\$750.00	\$1,500.00	\$900.00	\$1,800.00	\$600.00	\$1,200.00
12	Wet Connections (2-Inch), Includes Cut and Plug of Existing Pipes (all Sizes), with Backfill, Complete in Place.	1	EA.	\$400.00	\$400.00	\$232.30	\$232.30	\$500.00	\$500.00	\$400.00	\$400.00	\$300.00	\$300.00
13	Construct New Short Side Service Connection (3/4" or 1"), Including Tap, Pipe, Valves and Connection to Existing Meter, Complete in Place.	1	EA.	\$400.00	\$400.00	\$396.00	\$396.00	\$2,000.00	\$2,000.00	\$600.00	\$600.00	\$300.00	\$300.00
14	Construction New Long Side Service Connection (3/4" or 1") Including Tap, Pipe, Augered Construction Valves, and Connection to Existing Meter, Complete in Place.	1	EA.	\$500.00	\$500.00	\$745.70	\$745.70	\$2,600.00	\$2,600.00	\$1,200.00	\$1,200.00	\$400.00	\$400.00
15	Construct New Service Reconnection (3/4" or 1")(Long or Short), Including Tap, Pipe, Augered Construction, Valves and Connection To Existing Meter, Complete in Place.	1	EA.	\$500.00	\$500.00	\$745.70	\$745.70	\$2,650.00	\$2,650.00	\$1,200.00	\$1,200.00	\$400.00	\$400.00
16	Trench Safety System, Complete in Place.	326	L.F.	\$1.00	\$326.00	\$0.10	\$32.60	\$3.00	\$978.00	\$0.10	\$32.60	\$0.01	\$3.26

Bid Tabulation - Bid Opening, Thursday, March 4, 2010 at 2:00 P.M. City of La Porte South Broadway Waterline Replacement La Porte Bid No. 10021 LJA Project No. E170-0070	Page 2	D. L. Elliott Enterprises, Inc. 13405 S.W. Freeway, Ste 210 Sugar Land, TX 77478 PH: 281-277-4414 FAX: 281-277-3698 Darryl Elliott, President	Metro City Construction, L.P. 5715 Luce Street Houston, TX 77087 PH: 713-943-0090 FAX: 713-943-0092 Robert N. Smither, Chief Estim.	Mar-Con Services, LLC 1410 Preston Avenue, Bldg. H Pasadena, TX 77503 PH: 713-473-1800 FAX: 713-473-1811 Mario Ramos, Owner	Kingsley Constructors, Inc. 1544 Sawdust Rd., Suite 200 Houston, TX 77380 PH: 281-363-1979 FAX: 281-363-1993 Brad C. Kingsley, VP	Pro Line Service P.O. Box 6853 Kingwood, TX 77325 PH: 832-473-2905 FAX: 281-312-1346 Courtland Peacock, President
---	--------	--	--	--	--	--

ITEM NO.	DESCRIPTION	EST QTY	UNITS	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM
17	Traffic Control, as Necessary Along Broadway, Includes Acquiring Permits, Installation, Maintenance, and Removal of All Traffic control Devices Required by Permit and as Shown on Project Plans, Complete in Place.	1	L.S.	\$3,000.00	\$3,000.00	\$1,262.00	\$1,262.00	\$6,200.00	\$6,200.00	\$3,000.00	\$3,000.00	\$3,000.00	\$3,000.00
18	Turf Establishment Hydro-mulch Seeding, Complete in Place.	200	S.Y.	\$1.50	\$300.00	\$4.00	\$800.00	\$3.50	\$700.00	\$6.00	\$1,200.00	\$4.00	\$800.00
19	SWWPP, Inlet Protection Barrier, Installed, Maintained, and Removed, Complete in Place.	7	EA.	\$40.00	\$280.00	\$55.00	\$385.00	\$52.00	\$364.00	\$50.00	\$350.00	\$50.00	\$350.00
SUPPLEMENTARY ITEMS													
20	"Extra" Bank Sand, Complete in Place.	100	C.Y.	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00
21	"Extra" Crushed Limestone Bedding, Complete in Place.	50	C.Y.	\$25.00	\$1,250.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00
22	"Extra" Cement Stabilized Sand, 2.0 Sacks Per ton, Complete in Place.	5	TON	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00
23	"Extra" Class A concrete, Complete in Place.	25	C.Y.	\$100.00	\$2,500.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00
24	"Extra" Reinforcing Steel, Complete in Place.	250	LB.	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00
25	"Extra" Turf Establishment, Full Sodding, Complete in Place.	100	S.Y.	\$2.50	\$250.00	\$4.00	\$400.00	\$4.00	\$400.00	\$7.00	\$700.00	\$2.50	\$250.00

TOTAL Items 1 Through 25

\$138,858.00

\$148,999.10

\$163,256.00

\$166,726.60

\$183,655.26

Bid Tabulation - Bid Opening, Thursday, March 8, 2010 at 2:00 P.M.
 City of La Porte
 South Broadway Waterline Replacement
 La Porte Bid No. 10021
 LJA Project No. E170-0070

R. L. Utilities, Inc.
 P.O. Box 1154
 La Porte, TX 77572
 PH: 281-479-6567
 FAX: 281-476-9996
 Russell D. Lundemo, Pres.

M.J. Sheridan of Texas
 9015 Sweetbrush
 Houston, TX 77064
 PH: 281-469-5810
 FAX: 281-469-7476
 Jimmy Flores, VP

Reliance Construction Services
 4302 Almeda-Genoa Road
 Houston, TX 77048
 PH: 713-991-6685
 FAX: 713-991-6900
 H.S. Sidhu, President

Triple B. Services, L.L.P.
 820 Old Atascocita Rd.
 Huffman, TX 77336
 PH: 281-324-3264
 FAX: 281-324-1304
 Donna Burke, Sr. Proj. Adm.

Huff & Mitchell, Inc.
 13626
 Cypress, TX 77429
 PH: 281-304-9100
 FAX: 281-304-9107
 Chris Bonham, Proj. Mgr.

ITEM NO.	DESCRIPTION	EST. QTY.	UNITS	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	Unit Price	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM
1	8-Inch Waterline (PVC, AWWA C-900, DR-18) with Ductile Iron Fittings, Open Cut, Joint Restraints (as necessary), All Depths, Complete in Place.	300	L.F.	\$52.00	\$15,600.00	\$74.00	\$22,200.00	\$62.00	\$18,600.00	\$24.60	\$7,380.00	\$50.00	\$15,000.00
2	6-Inch Waterline (PVC, AWWA C-900, DR-18) with Ductile Iron Fittings, Open Cut, Joint Restraints (as necessary), All Depths, Complete in Place.	16	L.F.	\$72.00	\$1,152.00	\$107.00	\$1,712.00	50.00	\$800.00	128.00	\$2,048.00	40.00	\$640.00
3	2-Inch Waterline (PVC, Sch. 40 with Sch. 40 Fittings), Open Cut, Joint Restraints (as necessary), All Depths, Complete in Place.	18	L.F.	\$21.00	\$378.00	\$73.00	\$1,314.00	\$30.00	\$540.00	\$8.75	\$157.50	\$20.00	\$360.00
4	8-Inch Waterline, Augered Construction (PVC, AWWA C-900, DR-18) All Depths, Complete in Place.	2,388	L.F.	\$41.00	\$97,908.00	\$44.00	\$105,072.00	\$62.00	\$148,056.00	\$66.00	\$157,608.00	\$89.00	\$212,532.00
5	8" Gate Valve (AWWA) with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	7	EA.	\$1,200.00	\$8,400.00	\$1,600.00	\$11,200.00	\$1,125.00	\$7,875.00	\$1,450.00	\$10,150.00	\$1,750.00	\$12,250.00
6	2" Gate Valve (AWWA) with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	1	EA.	\$400.00	\$400.00	\$856.00	\$856.00	\$500.00	\$500.00	\$558.00	\$558.00	\$451.00	\$451.00
7	8" Tapping sleeve and Valve (AWWA) Full Body with Adjustable Box, Joint Restraint (as necessary), Accessories, Concrete Collar, Complete in Place.	1	EA.	\$5,500.00	\$5,500.00	\$6,850.00	\$6,850.00	\$4,600.00	\$4,600.00	\$9,700.00	\$9,700.00	\$5,000.00	\$5,000.00
8	Fire Hydrant Assembly, With Restrained Joints, 4-Foot Bury, Concrete Collar, Complete in Place.	5	EA.	\$4,000.00	\$20,000.00	\$5,000.00	\$25,000.00	\$3,000.00	\$15,000.00	\$4,185.00	\$20,925.00	\$3,000.00	\$15,000.00
9	Extra Depth Bury for Fire Hydrant, Complete in Place.	10	V.F.	\$100.00	\$1,000.00	\$50.00	\$500.00	\$100.00	\$1,000.00	\$76.00	\$760.00	\$300.00	\$3,000.00
10	Wet Connections (8-Inch), Includes Cut and Plug of Existing Pipes (All Sizes), With Backfill, Complete in Place.	3	EA.	\$3,200.00	\$9,600.00	\$1,600.00	\$4,800.00	\$1,100.00	\$3,300.00	\$1,000.00	\$3,000.00	\$1,800.00	\$5,400.00
11	Wet Connections (6-Inch), Includes Cut and Plug of Existing Pipes (all Sizes), with Backfill, Complete in Place.	2	EA.	\$2,500.00	\$5,000.00	\$1,500.00	\$3,000.00	\$1,000.00	\$2,000.00	\$834.00	\$1,668.00	\$1,200.00	\$2,400.00
12	Wet Connections (2-Inch), Includes Cut and Plug of Existing Pipes (all Sizes), with Backfill, Complete in Place.	1	EA.	\$1,000.00	\$1,000.00	\$750.00	\$750.00	\$900.00	\$900.00	\$175.00	\$175.00	\$1,000.00	\$1,000.00
13	Construct New Short Side Service Connection (3/4" or 1"), Including Tap, Pipe, Valves and Connection to Existing meter, Complete in Place.	1	EA.	\$1,500.00	\$1,500.00	\$600.00	\$600.00	\$500.00	\$500.00	\$556.00	\$556.00	\$1,500.00	\$1,500.00
14	Construction New Long Side Service Connection (3/4" or 1") Including Tap, Pipe, Augered Construction Valves, and Connection to Existing Meter, Complete in Place.	1	EA.	\$3,200.00	\$3,200.00	\$700.00	\$700.00	\$700.00	\$700.00	\$2,360.00	\$2,360.00	\$2,000.00	\$2,000.00
15	Construct New Service Reconnection (3/4" or 1")(Long or Short), Including Tap, Pipe, Augered Construction, Valves and Connection To Existing Meter, Complete in Place.	1	EA.	\$3,200.00	\$3,200.00	\$700.00	\$700.00	\$700.00	\$700.00	\$2,362.00	\$2,362.00	\$2,000.00	\$2,000.00
16	Trench Safety System, Complete in Place.	326	L.F.	\$3.00	\$978.00	\$1.00	\$326.00	\$0.01	\$3.26	\$5.00	\$1,630.00	\$1.00	\$326.00

Bid Tabulation - Bid Opening, Thursday, March 8, 2010 at 2:00 P.M. City of La Porte South Broadway Waterline Replacement La Porte Bid No. 10021 LJA Project No. E170-0070	Page 4	R. L. Utilities, Inc. P.O. Box 1154 La Porte, TX 77572 PH: 281-479-6567 FAX: 281-476-9996 Russell D. Lundemo, Pres.	M.J. Sheridan of Texas 9015 Sweetbrush Houston, TX 77064 PH: 281-469-5810 FAX: 281-469-7476 Jimmy Flores, VP	Reliance Construction Services 4302 Almeda-Genoa Road Houston, TX 77048 PH: 713-991-6685 FAX: 713-991-6900 H.S. Sidhu, President	Triple B. Services, L.L.P. 820 Old Atascocita Rd. Huffman, TX 77336 PH: 281-324-3264 FAX: 281-324-1304 Donna Burke, Sr. Proj. Adm.	Huff & Mitchell, Inc. 13626 Cypress, TX 77429 PH: 281-304-9100 FAX: 281-304-9107 Chris Bonham, Proj. Mgr.
---	--------	--	---	---	---	--

ITEM NO	DESCRIPTION	EST QTY	UNITS	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM	UNIT PRICE	TOTAL PRICE PER ITEM
17	Traffic Control, as Necessary Along Broadway, Includes Acquiring Permits, Installation, Maintenance, and Removal of All Traffic control Devices Required by Permit and as Shown on Project Plans, Complete in Place.	1	L.S.	\$3,500.00	\$3,500.00	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$31,000.00	\$31,000.00	\$3,000.00	\$3,000.00
18	Turf Establishment Hydro-mulch Seeding, Complete in Place.	200	S.Y.	\$5.00	\$1,000.00	\$6.00	\$1,200.00	\$2.50	\$500.00	\$11.00	\$2,200.00	\$10.00	\$2,000.00
19	SWWPP, Inlet Protection Barrier, Installed, Maintained, and Removed, Complete in Place.	7	EA.	\$500.00	\$3,500.00	\$55.00	\$385.00	\$25.00	\$175.00	\$104.00	\$728.00	\$50.00	\$350.00
SUPPLEMENTARY ITEMS													
20	"Extra" Bank Sand, Complete in Place.	100	C.Y.	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00
21	"Extra" Crushed Limestone Bedding, Complete in Place.	50	C.Y.	\$50.00	\$2,500.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00	\$25.00	\$1,250.00
22	"Extra" Cement Stabilized Sand, 2.0 Sacks Per ton,	5	TON	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00	\$30.00	\$150.00
23	"Extra" Class A Concrete, Complete in Place.	25	C.Y.	\$150.00	\$3,750.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00	\$100.00	\$2,500.00
24	"Extra" Reinforcing Steel, Complete in Place.	250	LB.	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00	\$1.00	\$250.00
25	"Extra" Turf Establishment, Full Sodding, Complete in	100	S.Y.	\$7.00	\$700.00	\$2.50	\$250.00	\$2.50	\$250.00	\$11.00	\$1,100.00	\$2.50	\$250.00

TOTAL Items 1 Through 25 **\$191,166.00** **\$194,065.00** **\$211,649.26** **\$261,215.50** **\$289,609.00**